CHITALDRUG DIVISION.

Dated 14th December 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 10th January 1930, for constructing Quarters for the Amildar at Davangere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st January 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Currency Notes, as earnest money and be superscribed "Tender for constructing Quarters for the Amildar at Davangere," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, Shimoga, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract showing the quantities for constructing quarters for Amildar at Davangere.

Sl. No.	Items of work	Per	Quantity	Rate
				Rs.
1	Earthwork excavation and filling in basement ...	Cyd.	191	
2	Stone jelly concrete	C.ft.	1,253	
3	Stone in clay foundation and basement	,,	4,226	
4	Burnt brick in clay	,,	4,112	
5	Burnt brick in mortar	,,	1,298	
6	Burnt stone slabs 6″ dressed and fixed	S.ft.	332	
7	Cut stone pillars 9″ square and 9½′ high with base and capitals.	No.	4	
8	Do do 6″ do and 7′ do do ...	,,	4	
9	Teakwood pannelled doors with fittings	S.ft.	71	
10	Do do battened do	,,	269	
11	Do windows ½ pannelled and ½ glazed single side in 4 halves including iron bars etc., complete.	,,	178	
12	Teakwood glazed ventilators with iron bars etc. ...	,,	54	
13	Do wall shelves with battened shutters, cross planks, etc.	,,	36	
14	Teakwood work wrought and put up with wood oiling and required tarring.	C.ft.	204·32	
15	Teakwood eave board with painting	R.ft.	107	
16	Cornice 9″ thick	,,	266	
17	Pukka terrace complete	Sqr.	11·50	
18	Roofing with Mangalore tiles on teak reepers, etc.	,,	12·05	
19	Ridge tiles set in mortar and cement pointed ...	R.ft.	78	
20	Parapet wall as per plan	,,	243	
21	Binding wall over terrace	,,	56	
22	Chunam plastering	Sqr.	90·00	
23	Cement pointing	,,	6.50	
24	White washing	,,	90·00	
25	Burnt brick in mortar coping including plastering ..	R.ft.	76	
26	Teakwood ½″ planking and zinc sheets for valleys ...	S.ft.	50	
27	Flooring with Mangalore tiles on 3″ concrete and cement pointing.	Sqr.	12·20	
28	Do 1½″ thick Cuddapah slabs over do do ...	,,	4·55	
29	Silicate painting 2 coats	,,	13·00	
30	Providing rain water spouts	Lump	sum	
31	Do drain pipes 1½″ dia. and 1½′ long ..	No.	18	
32	Do sinks	,,	4	
33	Do mortar and pestal stone	,,	2	
34	Do pendents	,,	6	
35	Do moulding around doors, windows, etc. ..	Lump	sum	
36	Clearing site and levelling ground, etc.	Lump	sum	
37	Constructing drains to lead off water ...	Lump		

Dated 15th December 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 10th January 1930, for constructing quarters for the Amildar at Molakalmuru. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st January 1931.

2. The plans. detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Currency Notes, as earnest money and be superscribed "Tender for constructing quarters for the Amildar at Molakalmuru," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract showing the quantities for constructing quarters for Amildar at Molakalmuru.

No.	Items of work	Per	Quantity	Rate Rs.
1	Earth work excavation and filling in basement ...	C.yd.	191	
2	Stone jelly concrete	C.ft.	1,253	
3	Stone in clay foundation and basement	,,	4,226	
4	Burnt brick in clay	,,	4,112	
5	Burnt brick in mortar	,,	1,298	
6	Burnt stone slabs 6" dressed and fixed	S.ft.	332	
7	Cut stone pillars 9" square and 9½' high with base and capitals.	No.	4	
8	Do do 6" do and 7' do do ..	,,	4	
9	Teakwood pannelled doors with fittings ...	S.ft.	71	
10	Do do battened do ...	,,	269	
11	Do windows ½ pannelled and ½ glazed single side in 4 halves including iron bars, etc., complete.	,,	178	
12	Teakwood glazed ventilators with iron bars etc. ..	,,	54	
13	Do wall shelves with battened shutters, cross planks, etc.	,,	36	
14	Do work wrought and put up with wood oiling and required tarring.	C.ft.	204·32	
15	Do eave board with painting	R.ft.	107	
16	Cornice 9" thick	,,	266	
17	Pukka terrace complete	Sqr.	11·50	
18	Roofing with Mangalore tiles on teak reepers, etc. ..	,,	12·05	
19	Ridge tiles set in mortar and cement pointed ...	R.ft.	78	
20	Parapet wall as per plan	,,	243	
21	Binding wall over terrace	,,	56	
22	Chunam plastering	Sqr.	90·00	
23	Cement pointing	,,	6·50	
24	White washing	,,	90·00	
25	Burnt brick in mortar coping including plastering ...	R.ft.	76	
26	Teakwood ½" planking and zinc sheets for valleys ...	S.ft.	50	
27	Flooring with Mangalore tiles on 3" concrete and cement pointing.	Sqr.	12·20	
28	Do 1½" thick Cuddapah slabs over do do ...	,,	4·55	
29	Silicate painting 2 coats	,,	13·00	
30	Providing rain water spouts	L. S.	...	
31	Do drain pipes 1½" dia and 1½' long ...	No.	18	
32	Do sinks	,,	4	
33	Do mortar and pestal stone	,,	2	
34	Do pendents	,,	6	
35	Do moulding around doors, windows etc. ...	Lump	sum	
36	Clearing site and levelling ground, etc. ...	Lump	sum	
37	Constructing drains to lead of water	Lump	sum	